

Office of the Municipal Councillors, Bhatpara

[Address: 1/1, West Ghoshpara Road, P.O. Kankinara, District: North 24 Parganas. PIN-743 126]
☎ 2581-2082, 2581-9515, 2581-9514. Fax: 2581-1318. Email : bhat_09@yahoo.com * bhatparamunicipality@gmail.com

Notice Inviting Tender

No:- I-4(F)/DR-2/1091.

Dated...16.5.2018

Sealed tender in specified printed tender form are invited by the Chairman / Executive Officer / Authorized Officer of the Bhatpara Municipality, Bhatpara, P.O.-Kankinara for the following work(s) from the eligible contractors as per particulars below.

1. A. a) Name of the work: Supplying, Erection & Commissioning of 16 mtrs long High Mast for Monimala Ground at ward no- 15 under Bhatpara Municipality.
- b) Contractor(s) eligible to submit tender:-
I) Bonafide outside contractors having sound Financial status and must have credential in similar nature of work in any Govt./ Semi-Govt. Organization of value not less than 30% of work under single contact within last 3 years having upto date valid IT, PT, GST registration.
II) Working contractors of Bhatpara Municipality who have successfully completed the job in last three years and have no pending job in hand under this municipality at present, having upto date valid IT, GST registration and PT, credential of 30% of similar nature of work may also be eligible to participate in this tender.
- c) Estimated value of work put to tender: Total Rs.3,94 ,026/-
- d) Initial earnest money 2% of estimated value (To be deposited by Cash/Bank Draft in favour of Chairman, Bhatpara Municipality):- Exempted for enlisted contractors.
- e) Time of completion: - 30 Days from the date of issue of Work Order.
- f) Price per copy of tender form:- 20.00
- g) Price per copy of set of other tender documents:- 1000.00
1. B. Last date of receiving application for permission of purchasing tender:- 25.05.2018 (upto 3:00 p.m.)
1. C. Last date and time limit for purchasing of tender:- 28.05.2018 (upto 3:00 p.m.)
1. D. Last date of submission of tender:- 30.05.2018 (upto 3:00 p.m.)
1. E. Date of opening of tender:- 30.05.2018 (at 3:30 p.m.)
1. F. Validity of Warranty: - Three year (all materials of High Mast)
1. G. Circle schedule of rates applicable for this work in respect of supplementary items of work or anything otherwise:- As per Drawing.
1. H. Mode of issue of tender papers: - Tender paper will be issued by the Executive Officer / Authorized Officer, Bhatpara Municipality.

Office of the Municipal Councillors, Bhatpara

[Address: 1/1, West Ghoshpara Road, P.O. Kankinara, District: North 24 Parganas. PIN-743 126]
☎ 2581-2082, 2581-9515, 2581-9514. Fax: 2581-1318. Email : bhat_09@yahoo.com * bhatparamunicipality@gmail.com

No:- I-4(F)/DR-2/1091..

Dated...16.5.2018

- All eligible and intending tenderers are required to produce before the Executive Officer/Authorised Officer valid income tax and P.tax etc. upto date clearance certificate in original along with the application for permission for issue of tender. Upto date valid GST. & P.T. clearance certificate in proper form shall be produced by the qualifying first three lowest tenderers on intimation after opening the tender. For the purpose of issue of tender from involving work, the intending outside tenderers who are otherwise eligible are required to produce the satisfaction of tender accepting authority credentials about past experience, financial stability special aptitude possession of equipment necessary for the type of work.
- The tender documents comprising of relevant printed tender forms/ declaration therefore. NIT specific priced schedule of items for the work and other tender documents may be seen at the Municipal Office on all working days (from Monday to Friday from 11 a.m. to 5 p.m.) and may be purchased from the said Officer during the same period on production of letter of permission issued by the Chairman/ Executive Officer.
- The contractors should quote in figures as well as in word the rate in percentage above/below or at per on the total amount of the priced schedule of items with probable quantities.
- The Contractor may sign either in English or Bengali or Hindi but the rate as above should also be quoted in the same language. In case of illiterate Contractors, the rate tendered for should be attested by a witness shown to the Tender Accepting Authority. Intending tenderer should obtain tender documents well in advance to guard against any difficulties due to possible absence from Head Quarters of the Officer issuing the tender papers.
- The Authority reserves the right to reject the lowest tender or all the tenders without assigning any reason and he is not bound to accept the lowest tender also.
- For details please visit our website:- www.bhatparamunicipality.in

Bhat
16-5-18

.....
Executive Officer
Bhatpara Municipality

Copy forwarded for information to:-

- Chairman, Bhatpara Municipality
- Vice - Chairperson, Bhatpara Municipality.
- President of Tender Committee. Bhatpara Municipality
- Sri / Smt. _____ (Member, Chairman-in-Council, Bhatpara Municipality)
- Finance Officer. Bhatpara Municipality.
- The Engineer, Bhatpara Municipality
- The Engineer (AE), Electrical Bhatpara Municipality)
- The Accountant, Bhatpara Municipality
- The Cashier, Bhatpara Municipality
- Notice Board of Bhatpara Municipality.
- The Head Clerk, Bhatpara Municipality
- IT co-ordinator, Bhatpara Municipality to upload the matter in our office Web portal immediately.
- "Do" Branch Office of Shyamnagar.

Bhat
16-5-18

.....
Executive officer
Bhatpara Municipality

Bhatpara Municipality

Schedule of work

Name of work:- Supply, erection and commissioning of 16 mtrs. long High Mast Pole with 6 nos 250 watt LED lights at Monimala Ground, ward no- 15 under Bhatpara Municipality.

SL	Description of Item	UNIT	Qty
1.00	Earth work in excavation of foundation trenches or drains in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoil within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, leveling, dressing and ramming the bottom, bailing out as required complete. Depth of excavation not exceeding 1,500 mm. [1 nos x 2.87 x 2.87 x 1.50]	%Cu.M	12.36
1.01	depth of excavation for additional depth beyond 1,500 mm. and 3,000 mm but not requiring shoring. [1 nos x 2.87 x 2.87 x 2.0]	%Cu.M	16.47
2.00	Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation [1 nos x 28.82 CUM]	%Cu.M	28.82
3.00	Single Brick Flat Soiling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand. [1 x 2.87 x 2.87]	Sq.M	8.24
4.00	Cement concrete with graded jhama khoa (30 mm size) excluding shuttering in ground floor and foundation. (a) 1 : 3 : 6 proportion. [1 nos x 1.375 cum]	Cu.M	1.37
5.00	Ordinary Cement concrete (mix 1 : 1 : 5 : 3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforced if any, in ground floor as per relevant IS codes. (i) Pakur Variety. [1 x 7.59 cum]	Cu.M	7.59
6.00	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc. initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation, basement and upto roof of ground floor/upto 4 m (i) For steel/Mild Steel ii. Other than SAIL/TATA/RINL [1 nos x 0.38 MT]	M.T	0.38
7.00	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof ground floor) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. [1 nos x 20.5 x Sq Mt]	Sqm	20.50

SL	Description of Item	UNIT	Qty
8.00	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing, and drip course. Scaffolding / staging where necessary (Ground Floor) (i) With 1:4 cement mortar (a) 10 mm thick plaster	Sq.M	3.00
9.00	Neat cement punning about 1.5 mm thick in wall, dado, window sill, floor etc. NOTE: cement 0.152 cu. m. per 100 sq. m. [1 nos x 3.0 Sq mt]	Sq.M	3.00
10.00	Supply of 16 M. High Mast system with its accessories, Mast shaft shall be given in 2 section, hot dip galvanized and suitable for wind velocity as per IS-875 part-3. It shall also incl. accessories. For High Mast incl. head frame, steel wire rope 6mm dia (7/19 construction), double drum winch galvanized lantern carriage arrangement suitable for 6-12 luminary symmetrical and its control gear boxes and lighting final. The mast shall have integral power tool system. Luminaries wiring materials include of foundation bolts manufactured from special steel along with nuts, washers, anchor plates and templates, delivery charges (lifting special type loading and unloading).	Each	1.00
11.00	Erection upto 20 mtrs. High Mast over the civil foundation bolts with the help of trolley fixed moving crane and maximum 10 nos. corrosion free nut-bolts etc. completed.	Each	1.00
12.00	Supplying and fixing 250 watts LED Flood Light. (1 x 6 nos)	Each	6.00
13.00	Fixing only Floodlight fitting with suitable clamps for mounting on pole/ tower similar structure. (1 x 6 nos)	Each	6.00
14.00	Supplying of 1.1 KV gr. PVC insulated aluminum conductor armoured 25 sq mm 4 cr. [1 nos x 75 mt]	R.M	75.00
15.00	Laying of one cable upto 50 sq mm through existing RCC/Hume/GI pipe open masonry trench for single 2.3.3.5 & 4 Cr. [1 nos x 75 Mt]	R.M	75.00
16.00	S & F medium gauge GI pipe (ISI-medium) protection with necessary fittings and jointing materials as required. (a) 80 mm dia.	R.M	75.00
17.00	Supplying and fixing compressor type gland complete with brass gland brass ring for dust & moisture proof entry of XLPE / PVC armoured cable as below. (a) For 3.5 cr. 25 sq mm	Set	2.00
18.00	Finishing the end of flowing XLPE/ PVC armoured cable by crimpling method incl. supplying and fixing solder less socket tapes anticorrosive paste and jointing materials. 3.5 core x 25 sq mm cable.	Set	2.00
19.00	Earthing with 50 mm dia GI pipe 3.64 mm thick x 3.04 mtrs. long and 1x4 SWG GI (hot-dip) wire (4mtrs. long) 13 mm dia, x 80mm long GI bolts, double nuts, double washers incl. S&F 15 mm dia GI pipe protection (1 mtrs. long) to be filled with bitumen partly under the ground level and partly above the ground level and restoring the surface duly rammed as below- (a) For soft soil by TATA Medium gauge G.I Pipe	Each	1.00

BK/2
16-5-18

Executive Officer
Bhatpara Municipality